BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Name of the Work :Improvements to Balance Roads and Drains AK Colony Singapura in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	KRIDL	
				In Figures	In Words
1	295.80	KSRRB M200-12.2 : Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable material with all lifts and lead and lead of 10000 meters complete as per specifications. lime/cement concrete, I.by manual means B. cement concrete grade M-15 & M-20. **No. 136 / Item No. 18.18 / PWD SR 2015-16**	Cum	Rs.375.24	Rupees Three Hundred and Seventy five and twenty four Paise only
2	418.18	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. **Page No. 141 / Item No. 19.1 / PWD SR 2015-16**	Cum	Rs.81.62	Rupees Eighty One and Sixty Two Paise only
3	438.75	Removing B.S Slab of Drain and stacking **Page No. 25 / Item No. 5.32 / PWD SR 2015-16**	Sqm	Rs.63.72	Rupees Sixty Three And Seventy Two paise only
4	438.75	Refixing stone slabs of drains and pointing in C.M (1:3) **Page No. 25 / Item No. 5.33 / PWD SR 2015-16**	Sqm	78.84	Rupees Seventy eight and Eighty Four Paise Only
5	68.40	KSRB 2.8 : Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications. Specification. No. KBS, **Page No. 6 / Item No. 2.15 / PWD SR 2015-16**	Cum	Rs.2,133.78	Rupees Two Thousand One Hundred and Thirty Three and Seventy Eight Paise Only
6	181.20	KSRB 4-1.3 : Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. **No. 12/ Item No. 4.3/ PWD SR 2015-16**	Cum	Rs.4,976.70	Rupees Four Thousand Nine Hundred seventy Six and Seventy Paise Only
7	1059.00	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface such as walls** at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 **Page No. 15 / Item No. 4.31 / PWD SR 2015-16**	Sqm	Rs.306.72	Rupees Three Hundred and Six and Seventy Two Paise only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
24/2/16

Sl. No.	Approved Qty.	Description	Unit	KRIDL	
				In Figures	In Words
8	247.90	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. **Page No. 18 / Item No. 4.48 / PWD SR 2015-16**	Cum	Rs.6,332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
9	12.54	KSRB 4.9.2 : Providing **T .M.T steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 **(Page No 17., I.No.4.46.2 of KPWD S.R 2015-16).**	Tonne	Rs.59,327.91	Rupees Fifty Nine Thousand Three Hundred and Twenty Seven Rupees Only
10	980.00	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. **174 / Item No. 22.7 / PWD SR 2015-16**	Sqm	Rs.97.20	Rupees Ninty Seven and Twenty Paise only
11	100.00	Providing **groove cutting** for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification **Concrete Pavement Page No. 175 / Item No. 22.8.1 / PWD SR 2015-16**	Sqm	Rs.124.20	Rupees One Hundred and Twenty Four and Twenty Paise only
12	228.00	Providing **and Fixing precast RCC slab s of 100 mm thick** including cost of all materials,labour,curing,transportation,loading unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	Rs.1,760.00	Rupees One Thouand seven Hundred and Sixty Only
13	422.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. **Page No. 25 / Item No. 5.30 / PWD SR 2015-16**	No.s	Rs.320.76	Rupees Three Hundred and Twenty and SeventySix Paise only
14	66.50	KSRB 15.19.1 : Providing and applying ready mix **priming coat over concrete** / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughtly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. **Page No. 121 / Item No. 15.80 / PWD SR 2015-16**	Sqm	Rs.27.00	Rupees Twenty Seven only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
21/x/16

Sl. No.	Approved Qty.	Description	Unit	KRIDL	
				In Figures	In Words
15	66.50	KSRB 15.20.1 : Providing and applying floor **painting with ready mix two coats** (Excluding priming coat) on new s concrete / masonry / asbestos cement sheet / / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. **Page No. 121 / Item No. 15.83 / PWD SR 2015-16**	Sqm	Rs.51.84	Rupees Fifty One and Eighty Four Paise only
16	418.18	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	Rs.100.08	Rupees One Hundred and Eight Paise only

I am prepared to execute the above mentioned work written by me in Schedule - B

EXECUTIVE ENGINEER-4
KRIDL, BMP DIVISION,
BANGALORE-560 010

Contractor Signature
Reg. No.
Postal Address

21/x/16

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92